

ทดลองงานที่มีปัญหา															
สัญญาเลขที่ ทดลอง ลงวันที่ จำนวนเงินตามสัญญา 0 บาท (ไม่รวมภาษีมูลค่าเพิ่ม) ผู้รับจ้าง สีเสภากรโยธา กำหนดแล้วเสร็จตามสัญญา วันที่										ค่าอุปกรณ์และขนส่ง		งวดที่ 1			
สำหรับผู้รับจ้าง										สำหรับการไฟฟ้าส่วนภูมิภาค					
ลำดับ	รายละเอียด	งานตามสัญญา				ส่งมอบงานครั้งนี้		รวมงานที่ส่งแล้ว (รวมครั้งนี้)		สรุปคณะกรรมการตรวจรับ		หมายเหตุ	เรียน คณะกรรมการตรวจรับงานจ้าง <input type="checkbox"/> ผลงานที่ส่งมอบครั้งนี้ มีรายละเอียดครบถ้วนถูกต้องตามข้อกำหนดในสัญญาทุกประการ <input type="checkbox"/> ผลงานที่ส่งมอบครั้งนี้ ก่อสร้างแล้วเสร็จเมื่อวันที่ <input type="checkbox"/> งานแล้วเสร็จภายในกำหนดเวลาตามสัญญา <input type="checkbox"/> งานแล้วเสร็จช้ากว่ากำหนดตามสัญญา.....วัน ลงชื่อ ผู้ควบคุมงาน () ตำแหน่ง วันที่		
		จำนวน	หน่วย	ค่าอุปกรณ์ต่อหน่วย	ค่าขนส่งต่อหน่วย	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)	จำนวน			เป็นเงิน (บาท)	
	PART A งานติดตั้งอุปกรณ์สถานีไฟฟ้า														
1	115 kV Gas Insulated Switchgear														
	- 123 kV, Gas Insulated Switchgear, 2500 A, 40 kA (Line Bay)	1	Set	5,303,872.00	55,000.00	5,358,872.00		-		-		-			
	- 123 kV, Gas Insulated Switchgear, 2500 A, 40 kA (TP Bay)	2	Set	4,855,872.00	55,000.00	9,821,744.00		-		-		-			
	- Local control panel	3	Set	Include		Include		-		-		-			
	- steel support structure	1	Lot	Include		Include		-		-		-			
	- 115 kV Indoor terminator kit for 115 kV GIS, 800 sq.mm H.V. power cable : 3pcs./set	2	Set	621,600.00	Include	1,243,200.00		-		-		-			
	- SF6 Filling & SF6 Leakage Test	1	Lot	Include		Include		-		-		-			
	- Earthing material for connection to the main earthing system (copper rope plus clamps)	1	Lot	Include		Include		-		-		-			
	- Supervision for installation , test and commissioning	1	Lot	N/A		N/A		-		-		-			
	- Control cable between 115 kV GIS and local control panel	1	Lot	Include		Include		-		-		-			
	- 115 kV GIS individual test	1	Lot	N/A		N/A		-		-		-			
	- Handle for cranking and wall plate or cubicle for tool storage	1	Lot	Include		Include		-		-		-			
2	115 kV Outdoor Terminator (at 115 kV UG Riser and TR)														
	- 115 kV Outdoor terminator for 800 sq.mm H.V. power cable, polymer insulator, creepage distance 31.5 mm/kV : 3pcs./set	2	Set	520,800.00	16,500.00	1,074,600.00		-		-		-			
	- 115 kV Outdoor terminator supporting structure at TR room (3 phases/set)	1	Set	50,400.00	2,750.00	53,150.00		-		-		-			
3	96 kV 10 kA Lightning arrester with counter (at 115 kV UG Riser and TR)														
	- 96 kV 10 kA Lightning arrester, Creepage distance 31.5 mm/kV and insulating base and surge counter	6	Set	106,400.00	2,750.00	654,900.00		-		-		-			
4	115 kV Control & Protection Board with annunciator														
	- Line control and protection board	1	Set	1,736,000.00	2,750.00	1,738,750.00		-		-		-			
	- Transformer control and protection board	2	Set	1,344,000.00	2,750.00	2,693,500.00		-		-		-			
	- Outdoor alarm (horn & siren)	1	Set	1,680.00	550.00	2,230.00		-		-		-			
	- Software to link between relay and computer to download data, setting from relay	1	Lot	Include		Include		-		-		-			
	- Test plug for testing relay 1 set, metering 1 set	1	Lot	Include		Include		-		-		-			
5	Computer-Based Substation Control System (CSCS)														
	- CSCS Panel	1	Set	2,217,600.00	5,500.00	2,223,100.00		-		-		-			
	- Workstation for CSCS control	1	Set	44,800.00	5,500.00	50,300.00		-		-		-			
	- Hard wiring, fiber optic, UTP Cable and accessories	1	Lot	Include		Include		-		-		-			
6	10 kV Indoor Air Insulated Switchgear 3150 A														
	- 10 kV Incoming cubicle with Potential Transformer (3150A)	2	Unit	997,696.00	2,750.00	2,000,892.00		-		-		-			
	รวม (1)					26,915,238.00		0.00		0.00		0.00			
เจ้าหน้าที่ผู้ได้รับมอบอำนาจจากผู้รับจ้าง		ผู้ควบคุมงาน													
ลงชื่อ.....		ลงชื่อ.....													
() ผู้จัดการโครงการ		() ตำแหน่ง													
วันที่		วันที่													

ทดลองงานที่มีปัญหา															
สัญญาเลขที่ ทดลอง ลงวันที่ จำนวนเงินตามสัญญา 0 บาท (ไม่รวมภาษีมูลค่าเพิ่ม) ผู้รับจ้าง สีเสกาการโยธา กำหนดแล้วเสร็จตามสัญญา วันที่										ค่าอุปกรณ์และขนส่ง		งวดที่ 1			
สำหรับผู้รับจ้าง										สำหรับการไฟฟ้าส่วนภูมิภาค					
ลำดับ	รายละเอียด	งานตามสัญญา				ส่งมอบงานครั้งนี้		รวมงานที่ส่งแล้ว (รวมครั้งนี้)		สรุปคณะกรรมการตรวจรับ		หมายเหตุ	เรียน คณะกรรมการตรวจรับงานจ้าง <input type="checkbox"/> ผลงานที่ส่งมอบครั้งนี้ มีรายละเอียดครบถ้วนถูกต้องตามข้อกำหนดในสัญญาทุกประการ <input type="checkbox"/> ผลงานที่ส่งมอบครั้งนี้ ก่อสร้างแล้วเสร็จเมื่อวันที่ <input type="checkbox"/> งานแล้วเสร็จภายในกำหนดเวลาตามสัญญา <input type="checkbox"/> งานแล้วเสร็จช้ากว่ากำหนดตามสัญญา.....วัน ลงชื่อ ผู้ควบคุมงาน () ตำแหน่ง วันที่		
		จำนวน	หน่วย	ค่าอุปกรณ์ ต่อหน่วย	ค่าขนส่ง ต่อหน่วย	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)	จำนวน			เป็นเงิน (บาท)	
	- 10 kV Outgoing cubicle (1250A)	16	Unit	921,872.00	2,750.00	14,793,952.00		-		-		-			
	- 10 kV Bus tie cubicle with potential transformer (3150A)	1	Unit	1,383,200.00	2,750.00	1,385,950.00		-		-		-			
	- 10 kV Disconnecting switch cubicle with potential transformer (3150A)	1	Unit	1,266,720.00	2,750.00	1,269,470.00		-		-		-			
	- 10 kV Load break switch (630A) Cubicle with fuse	1	Unit	616,000.00	2,750.00	618,750.00		-		-		-			
	- Arc detection system (fiber optic 3 compartment per 1 cubicle),	1	Lot	Include		Include		-		-		-			
	- Heater in 4 compartment per cubicle, Cable gland	1	Lot	Include		Include		-		-		-			
	- Supervisor for installation and support site test	1	Lot	N/A		N/A		-		-		-			
	- Wall plate for tool storage	1	Lot	Include		Include		-		-		-			
	- C base fame support 10 kV switchgear equipment	1	Lot	Include		Include		-		-		-			
	- Handle for cranking, Mobile Truck	1	Lot	Include		Include		-		-		-			
	- Software to link between relay and computer to download data, setting from relay	1	Lot	Include		Include		-		-		-			
	- Test plug for testing relay 1 set, metering 1 set	1	Lot	Include		Include		-		-		-			
7	Power Transformer														
	- 115/10 kV 3 phase ONAN/ONAF 25/27.5 MVA , Dyn1 with automatic OLTC with oil purifier for OLTC,	1	Unit	12,880,000.00	440,000.00	13,320,000.00		-		-		-			
	CT core in MV for winding temp and AVR, N bushing for protection														
	- Local control cubicle with lamp indicator and annanciator	1	Unit	Include		Include		-		-		-			
8	10/0.4 kV Station Service Transformer														
	- Station service transformer, oil-immersed type,three-phase , 100 kVA, Dyn11, 10,000-400/230 VAC	1	Set	145,600.00	8,800.00	154,400.00		-		-		-			
	with cable connection boxes														
9	AC and DC Distribution Board														
	- AC Distribution Board (2 main CB, 30 branch circuits), Floor type	1	Set	112,000.00	2,750.00	114,750.00		-		-		-			
	- DC Distribution Board (2 main CB, 30 branch circuits), Floor type	1	Set	134,400.00	2,750.00	137,150.00		-		-		-			
10	Battery & Battery Charger For 125 VDC														
	- Sealed Lead Acid Type Battery > 110 Ah 12V/block 125Vdc	1	Lot	205,520.00	2,750.00	208,270.00		-		-		-			
	- Steel Support for battery	1	Lot	Include		Include		-		-		-			
	- Battery Charger 30 A with automatic dropper switch	2	Set	123,200.00	2,750.00	251,900.00		-		-		-			
	- Safety switch with fuse	1	Set	3,920.00	1,100.00	5,020.00		-		-		-			
11	Power Cable & Termination kit														
	- H.V. power cable, 800 sq.mm., 115 kV, for connecting between 115 kV UG riser and 115 kV indoor GIS	1	Lot	1,593,648.00	27,500.00	1,621,148.00		-		-		-			
	(3 wires/phase)														
	รวม (2)					33,880,760.00		0.00		0.00		0.00			
เจ้าหน้าที่ผู้ได้รับมอบอำนาจจากผู้รับจ้าง		ผู้ควบคุมงาน													
ลงชื่อ.....		ลงชื่อ.....													
() ผู้จัดการโครงการ		() ตำแหน่ง													
วันที่		วันที่													

ทดลองงานที่มีปัญหา														ค่าอุปกรณ์และขนส่ง		งวดที่ 1	
สัญญาเลขที่ ทดลอง ลงวันที่ จำนวนเงินตามสัญญา 0 บาท (ไม่รวมภาษีมูลค่าเพิ่ม) ผู้รับจ้าง สีเสภากรโยธา กำหนดแล้วเสร็จตามสัญญา วันที่														สำหรับการไฟฟ้าส่วนภูมิภาค			
สำหรับผู้รับจ้าง																	
ลำดับ	รายละเอียด	งานตามสัญญา					ส่งมอบงานครั้งนี้		รวมงานที่ส่งแล้ว (รวมครั้งนี้)		สรุปคณะกรรมการตรวจรับ		หมายเหตุ	เรียน คณะกรรมการตรวจรับงานจ้าง <input type="checkbox"/> ผลงานที่ส่งมอบครั้งนี้ มีรายละเอียดครบถ้วนถูกต้องตามข้อกำหนดในสัญญาทุกประการ <input type="checkbox"/> ผลงานที่ส่งมอบครั้งนี้ ก่อสร้างแล้วเสร็จเมื่อวันที่ <input type="checkbox"/> งานแล้วเสร็จภายในกำหนดเวลาตามสัญญา <input type="checkbox"/> งานแล้วเสร็จช้ากว่ากำหนดตามสัญญา.....วัน ลงชื่อ ผู้ควบคุมงาน () ตำแหน่ง วันที่			
		จำนวน	หน่วย	ค่าอุปกรณ์ต่อหน่วย	ค่าขนส่งต่อหน่วย	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)					
	- H.V. power cable, 800 sq.mm., 115 kV, for connecting between 115 kV indoor GIS and power transformers (3 wires/phase)	1	Lot	312,480.00	5,500.00	317,980.00		-		-		-					
	- H.V. power cable, 500 sq.mm., 10 kV, for connecting between power transformer and 10 kV switchgear incoming cubicle (3 wires/phase)	1	Lot	518,000.00	8,800.00	526,800.00		-		-		-					
	- H.V. power cable, 500 sq.mm., 10 kV, for connecting between 10 kV switchgear bus tie circuit breaker cubicle and 10 kV switchgear disconnecting switch cubicle (3 wires/phase)	1	Lot	350,000.00	8,800.00	358,800.00		-		-		-					
	- H.V. power cable, 50 sq.mm., 10 kV, for connecting between 10 kV switchgear load break switch cubicle and station service transformer (1 wire/phase)	1	Lot	26,880.00	5,500.00	32,380.00		-		-		-					
	- Outdoor cable termination kit, for H.V. power cable, 500 sq.mm., 10 kV, completed with accessories.	9	Set	3,114.00	550.00	32,976.00		-		-		-					
	- Outdoor cable termination kit, for H.V. power cable, 50 sq.mm., 10 kV, completed with accessories.	3	Set	2,072.00	550.00	7,866.00		-		-		-					
	- Indoor cable termination kit, for H.V. power cable, 500 sq.mm., 10 kV, completed with accessories.	27	Set	1,882.00	550.00	65,664.00		-		-		-					
	- Indoor cable termination kit, for H.V. power cable, 50 sq.mm., 10 kV, completed with accessories.	3	Set	1,456.00	550.00	6,018.00		-		-		-					
	- Steel support for H.V. power cable under 10 kV switchgear (all cubicle) completed with wooden clamp	1	Lot	95,200.00	19,800.00	115,000.00		-		-		-					
12	Aluminium Conductor & accessories																
	- Stranded conductor, aluminium conductor 400 SQ.mm. and accessories, for connecting between outdoor cable terminator kit and power transformer, lightning arrester	1	Lot	8,960.00	1,100.00	10,060.00		-		-		-					
	- Substation connectors.	1	Lot	22,400.00	2,750.00	25,150.00		-		-		-					
	- Stranded conductor accessories.	1	Lot	4,480.00	1,100.00	5,580.00		-		-		-					
13	Cable Ladder & conduit for substation																
	- Rigid steel conduits, fittings and accessories	1	Lot	16,800.00	2,200.00	19,000.00		-		-		-					
	- Cable tray and cable ladder & fixing material	1	Lot	280,000.00	13,200.00	293,200.00		-		-		-					
	- Identification plates and danger notice	1	Lot	50,400.00	2,750.00	53,150.00		-		-		-					
	- Other necessary materials	1	Lot	11,500.00	3,167.00	14,667.00		-		-		-					
14	Grounding System																
	- Lightning protection	1	Lot	168,000.00	5,500.00	173,500.00		-		-		-					
	- Ground bar, PVC, RSC and accessories	1	Lot	5,600.00	1,100.00	6,700.00		-		-		-					
	- Ground mesh for 115/10 kV substation	1	Lot	39,200.00	2,750.00	41,950.00		-		-		-					
	- Ground rod, copper cover steel, dia. 16 mm. 3 m. long	1	Lot	47,040.00	5,500.00	52,540.00		-		-		-					
	- Conductor, copper, Bare 120 sq.mm.	1	Lot	705,600.00	13,200.00	718,800.00		-		-		-					
	- Earthing test pit.	2	Unit	2,800.00	550.00	6,700.00		-		-		-					
	รวม (3)					2,884,481.00		0.00		0.00		0.00					
เจ้าหน้าที่ผู้ได้รับมอบอำนาจจากผู้รับจ้าง ลงชื่อ..... () ผู้จัดการโครงการ วันที่		ผู้ควบคุมงาน ลงชื่อ..... () ตำแหน่ง วันที่															

ทดลองงานที่มีปัญหา														คำอุปกรณ์และขนส่ง	งวดที่ 1
สัญญาเลขที่ ทดลอง ลงวันที่ จำนวนเงินตามสัญญา 0 บาท (ไม่รวมภาษีมูลค่าเพิ่ม) ผู้รับจ้าง สีเสภากรโยธา กำหนดแล้วเสร็จตามสัญญา วันที่									สำหรับการไฟฟ้าส่วนภูมิภาค						
ลำดับ	รายละเอียด	งานตามสัญญา					ส่งมอบงานครั้งนี้		รวมงานที่ส่งแล้ว (รวมครั้งนี้)		สรุปคณะกรรมการตรวจรับ		หมายเหตุ	เรียน คณะกรรมการตรวจรับงานจ้าง <input type="checkbox"/> ผลงานที่ส่งมอบครั้งนี้ มีรายละเอียดครบถ้วนถูกต้องตามข้อกำหนดในสัญญาทุกประการ <input type="checkbox"/> ผลงานที่ส่งมอบครั้งนี้ ก่อสร้างแล้วเสร็จเมื่อวันที่ <input type="checkbox"/> งานแล้วเสร็จภายในกำหนดเวลาตามสัญญา <input type="checkbox"/> งานแล้วเสร็จช้ากว่ากำหนดตามสัญญา.....วัน ลงชื่อ ผู้ควบคุมงาน () ตำแหน่ง วันที่	
		จำนวน	หน่วย	คำอุปกรณ์ ต่อหน่วย	ค่าขนส่ง ต่อหน่วย	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)			
15	Cable & Accessories for Substation														
	- LV.power cable, 750 V, for connecting between AC distribution board and station service transformer /	1	Lot	33,600.00	2,750.00	36,350.00		-		-		-			
	substation lighting / AC consumption equipment														
	- LV.power cable, 750 V, for connecting between AC distribution board and outside LV function box	1	Lot	16,800.00	2,750.00	19,550.00		-		-		-			
	- LV.power cable, 750 V, for connecting between the DC distribution board and battery charger, battery charger	1	Lot	16,800.00	2,750.00	19,550.00		-		-		-			
	and safety switch, safety swith and battery, DC distribution board and DC consumption equipment														
	- Control cable, 750 V, for connecting between all equipment in substation for 115kV GIS local control panel,	1	Lot	470,400.00	8,800.00	479,200.00		-		-		-			
	power transformer local control board, power transformer remote control board, main control board,														
	CSCS panel, marshalling, AC board, DC board, battery charger, outdoor horn/siren, revenue meter panel														
	and 10 kV Switchgear														
	- Fire barrier system in control building	1	Lot	56,000.00	8,800.00	64,800.00		-		-		-			
16	Factory Test														
	- CT and VT accuracy test at factory 5 persons	1	Lot	N/A		N/A		-		-		-			
	- 115 kV Control & Protection Board	1	Lot	N/A		N/A		-		-		-			
	- 10 kV Indoor Air Insulated Switchgear at factory 5 persons	1	Lot	N/A		N/A		-		-		-			
	- Power Transformer Routine test, type test, special test and site test	1	Lot	N/A		N/A		-		-		-			
	- Power cable (115 kV XLPE cable)	1	Lot	N/A		N/A		-		-		-			
	- Battery Charger	1	Lot	N/A		N/A		-		-		-			
	- AC and DC distribution board	1	Lot	N/A		N/A		-		-		-			
17	Design engineering														
	- Electrical design engineering	1	Lot	Include		Include		-		-		-			
	- As built drawing	1	Lot	Include		Include		-		-		-			
18	Commissioning and training														
	- Commissioning & functest test	1	Lot	504,000.00	55,000.00	559,000.00		-		-		-			
	- 500 kVA Generator and 250kVA, 22/0.4kV transformer for back energized AC withstand	1	Lot	201,600.00	13,200.00	214,800.00		-		-		-			
	- Training (20 persons 3 day on the site training, break and lunch)	1	Lot	Include		Include		-		-		-			
	PART B งานโยธาสถานีไฟฟ้า														
1	Sub-soil test from ground surface to not less than 30.00 m. depth.	2	Bores	29,120.00	Include	58,240.00		-		-		-			
2	Control building														
	- Piling work include dynamic test (design by contractor)	1	Lot	586,992.00	Include	586,992.00		-		-		-			
	รวม (4)					2,038,482.00		0.00		0.00		0.00			
เจ้าหน้าที่ผู้ได้รับมอบอำนาจจากผู้รับจ้าง		ผู้ควบคุมงาน													
ลงชื่อ..... () ผู้จัดการโครงการ วันที่		ลงชื่อ..... () ตำแหน่ง วันที่													

ทดลองงานที่มีปัญหา															
สัญญาเลขที่ ทดลอง ลงวันที่ จำนวนเงินตามสัญญา 0 บาท (ไม่รวมภาษีมูลค่าเพิ่ม) ผู้รับจ้าง สีเสกากรโยธา กำหนดแล้วเสร็จตามสัญญา วันที่										ค่าอุปกรณ์และขนส่ง		งวดที่ 1			
สำหรับผู้รับจ้าง										สำหรับการไฟฟ้าส่วนภูมิภาค					
ลำดับ	รายละเอียด	งานตามสัญญา					ส่งมอบงานครั้งนี้		รวมงานที่ส่งแล้ว (รวมครั้งนี้)		สรุปคณะกรรมการตรวจรับ		หมายเหตุ		
		จำนวน	หน่วย	ค่าอุปกรณ์ ต่อหน่วย	ค่าขนส่ง ต่อหน่วย	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)			
	- Control building (not less than 14 x 18 Sq.mm.)	1	Lot	9,016,000.00	Include	9,016,000.00		-		-		-		<div>เรียน คณะกรรมการตรวจรับงานจ้าง</div> <div><input type="checkbox"/> ผลงานที่ส่งมอบครั้งนี้ มีรายละเอียดครบถ้วนถูกต้องตามข้อกำหนดในสัญญาทุกประการ</div> <div><input type="checkbox"/> ผลงานที่ส่งมอบครั้งนี้ ก่อสร้างแล้วเสร็จเมื่อวันที่</div> <div><input type="checkbox"/> งานแล้วเสร็จภายในกำหนดเวลาตามสัญญา</div> <div><input type="checkbox"/> งานแล้วเสร็จช้ากว่ากำหนดตามสัญญา.....วัน</div> <div>ลงชื่อ ผู้ควบคุมงาน</div> <div>() ตำแหน่ง</div> <div>วันที่</div>	
	- Epoxy floor (green/red color), self leveling	1	Lot	149,811.00	Include	149,811.00		-		-		-			
	- Power transformer room (Fire protection)	2	Set	604,778.00	Include	1,209,556.00		-		-		-			
	- Conduit for lightning protection	1	Lot	5,600.00	Include	5,600.00		-		-		-			
	- Earthing system in control building (steel strip size 25 x 4 mm)	1	Lot	49,694.00	Include	49,694.00		-		-		-			
	- Piping and drainage system	1	Lot	313,600.00	Include	313,600.00		-		-		-			
	- 3-Direction electric overhead crane 5 tons in 115 kV GIS room	1	Set	912,800.00	Include	912,800.00		-		-		-			
3	Facility for control building														
	- Load center 18 CKT with main CB 60 AT, 3P	1	Set	24,640.00	Include	24,640.00		-		-		-			
	- 1 x T8 16 watt LED lighting fixture (WP) in 115 kV GIS room	16	Set	1,680.00	Include	26,880.00		-		-		-			
	- 2 x T8 16 watt LED lighting fixture with Aluminum Louver in control room	12	Set	1,994.00	Include	23,928.00		-		-		-			
	- 2 x T8 16 watt LED lighting fixture with Acylic ditnsr in 10 kV SWG room	18	Set	2,464.00	Include	44,352.00		-		-		-			
	- 2 x T8 16 watt LED lighting fixture, Explosion proof light in battery room	1	Set	10,080.00	Include	10,080.00		-		-		-			
	- 1 x T8 16 watt LED lighting fixture bare type in Cable room	30	Set	997.00	Include	29,910.00		-		-		-			
	- 2 x T8 16 watt LED lighting fixture (WP) in Porch area around building	20	Set	1,848.00	Include	36,960.00		-		-		-			
	- 100 watt LED floodlight luminaires, in power transformer room	4	Set	7,784.00	Include	31,136.00		-		-		-			
	- Receptacle	20	Set	280.00	Include	5,600.00		-		-		-			
	- Power plug 3P+N+G 20A at 115 kV GIS & 10 kV SWG Room	2	Set	2,800.00	Include	5,600.00		-		-		-			
	- Safety switch for CDU (Air condition)	5	Set	5,040.00	Include	25,200.00		-		-		-			
	- Air condition 36,000 Btu (control room 2 set and 10kV SWG room 3 set)	5	Set	50,400.00	Include	252,000.00		-		-		-			
	- Air condition timer control panel	1	Set	16,800.00	Include	16,800.00		-		-		-			
	- Ventilation (Fan) + hood for rain protection in control building	1	Lot	201,600.00	Include	201,600.00		-		-		-			
	- Emergency lighting 2x50 w	10	Set	1,714.00	Include	17,140.00		-		-		-			
	- Emergency exiting	5	Set	1,848.00	Include	9,240.00		-		-		-			
	- Switch, wire, conductor, conduits and accessories	1	Lot	95,200.00	Include	95,200.00		-		-		-			
	- Steel roller door (Moter driver)	3	Set	64,400.00	Include	193,200.00		-		-		-			
	- Fire extinguisher (CO2)	6	Set	2,800.00	Include	16,800.00		-		-		-			
4	Fire alarm system & fire protection system														
	- Hardwire system 5 Zone (Manual ,Detector)	1	Set	44,800.00	Include	44,800.00		-		-		-			
	- Smoke detector (Control building)	14	Set	896.00	Include	12,544.00		-		-		-			
	รวม (5)					12,780,671.00		0.00		0.00		0.00			
เจ้าหน้าที่ผู้ได้รับมอบอำนาจจากผู้รับจ้าง		ผู้ควบคุมงาน													
ลงชื่อ.....		ลงชื่อ.....													
() ผู้จัดการโครงการ		() ตำแหน่ง													
วันที่		วันที่													

ทดลองงานที่มีปัญหา														สัญญาเลขที่ ทดลอง ลงวันที่ จำนวนเงินตามสัญญา 0 บาท (ไม่รวมภาษีมูลค่าเพิ่ม) ผู้รับจ้าง สีเสกาการโยธา กำหนดแล้วเสร็จตามสัญญา วันที่		ค่าอุปกรณ์และขนส่ง		งวดที่ 1					
สำหรับผู้รับจ้าง														สำหรับการไฟฟ้าส่วนภูมิภาค									
ลำดับ	รายละเอียด	งานตามสัญญา					ส่งมอบงานครั้งนี้		รวมงานที่ส่งแล้ว (รวมครั้งนี้)		สรุปคณะกรรมการตรวจรับ		หมายเหตุ	เรียน คณะกรรมการตรวจรับงานจ้าง <input type="checkbox"/> ผลงานที่ส่งมอบครั้งนี้ มีรายละเอียดครบถ้วนถูกต้องตามข้อกำหนดในสัญญาทุกประการ <input type="checkbox"/> ผลงานที่ส่งมอบครั้งนี้ ก่อสร้างแล้วเสร็จเมื่อวันที่ <input type="checkbox"/> งานแล้วเสร็จภายในกำหนดเวลาตามสัญญา <input type="checkbox"/> งานแล้วเสร็จช้ากว่ากำหนดตามสัญญา.....วัน ลงชื่อ ผู้ควบคุมงาน () ตำแหน่ง วันที่									
		จำนวน	หน่วย	ค่าอุปกรณ์ต่อหน่วย	ค่าขนส่งต่อหน่วย	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)											
	- Heat detector (Battery room)	1	set	4,200.00	Include	4,200.00		-		-		-											
	- Manual detector	6	set	1,176.00	Include	7,056.00		-		-		-											
	- Bell alarm	3	Set	896.00	Include	2,688.00		-		-		-											
	- Fire resistance wire conductor, wire conductor, conduits and accessories	1	Lot	39,200.00	Include	39,200.00		-		-		-											
5	115-10 kV Transformer foundation with RC. oil gutter.	2	Set	616,000.00	Include	1,232,000.00		-		-		-											
6	Steel cover around of RC. Oil gutter around transformer gutter	2	Set	134,400.00	Include	268,800.00		-		-		-											
7	Oil collecting pit and oil separator capacity not less than 25 cu.m., on pile	1	Set	504,000.00	Include	504,000.00		-		-		-											
8	2 set of steel pipes dia 6 inch	10	m	1,344.00	Include	13,440.00		-		-		-											
9	Station service transformer foundation	1	Set	28,000.00	Include	28,000.00		-		-		-											
10	Lamp Post Foundation on pile	6	Set	25,536.00	Include	153,216.00		-		-		-											
11	Cable trench Type A with steel cover, size 1.20 m	30	m	5,824.00	Include	174,720.00		-		-		-											
12	HDPE Dia 63 mm. PN8 and accessories (for Lamp circuit)	1	Lot	3,920.00	Include	3,920.00		-		-		-											
13	Crushed rock no.2 surfacing on area 23x31 Sq.mm., 0.10 m hight with concrete curve	1	Lot	30,464.00	Include	30,464.00		-		-		-											
14	RC pipe, PVC. pipe and RC manhole (All drainage system from control building, RC trench, oil collecting pit and oil separator etc.)	1	Lot	313,600.00	Include	313,600.00		-		-		-											
15	Wire mesh fence with door for power transformer	2	Set	112,000.00	Include	224,000.00		-		-		-											
16	Concrete with wire mesh fence on pile	100	m	6,880.00	Include	688,000.00		-		-		-											
17	Mesh gate (1 set x Rolling door) 6 m width	2	set	134,400.00	Include	268,800.00		-		-		-											
18	Civil engineering design and construction permissive fee (architech , civil , electrical)	1	Lot	168,000.00	Include	168,000.00		-		-		-											
19	Temporary fence and toilet	1	Lot	280,000.00	Include	280,000.00		-		-		-											
	PART C งานก่อสร้างสายส่งระบบ 115 เควี																						
1	Pole concrete 22.00 m. long with ground plate	8	each	28,000.00	2,750.00	246,000.00		-		-		-											
2	Foundation for pole concrete 22.00 m. long,																						
	- F1/1 or F6 with grounding (by contractor design)	8	Set	31,920.00	2,750.00	277,360.00		-		-		-											
3	Top pole installation																						
	- SS-SW-2 (exclude 115 kV Air break switch)	1	set	108,640.00	1,650.00	110,290.00		-		-		-											
	- SS-TG-5	2	set	29,662.00	1,650.00	62,624.00		-		-		-											
	- SS-TG-2	3	set	28,560.00	1,650.00	90,630.00		-		-		-											
	- SS-UG-1 (exclude terminator and lightning arrester)	1	set	655,200.00	5,500.00	660,700.00		-		-		-											
4	115 kV Air Break Switch																						
	- 123 kV, 2000 A, 40 kA Air break switch with steel support structure and operating platform	1	Set	532,000.00	8,800.00	540,800.00		-		-		-											
	รวม (6)						6,392,508.00	0.00		0.00		0.00											
เจ้าหน้าที่ผู้ได้รับมอบอำนาจจากผู้รับจ้าง		ผู้ควบคุมงาน																					
ลงชื่อ.....		ลงชื่อ.....																					
() ผู้จัดการโครงการ		() ตำแหน่ง																					
วันที่		วันที่																					

ทดลองงานที่มีปัญหา													คำติดตั้งและทดสอบ		งวดที่ 1	
สำหรับผู้รับจ้าง								สำหรับการไฟฟ้าส่วนภูมิภาค								
ลำดับ	รายละเอียด	งานตามสัญญา				ส่งมอบงานครั้งนี้		รวมงานที่ส่งแล้ว (รวมครั้งนี้)		สรุปคณะกรรมการตรวจรับ		หมายเหตุ	<div>เรียน คณะกรรมการตรวจรับงานจ้าง</div> <div><input type="checkbox"/> ผลงานที่ส่งมอบครั้งนี้ มีรายละเอียดครบถ้วนถูกต้องตามข้อกำหนดในสัญญาทุกประการ</div> <div><input type="checkbox"/> ผลงานที่ส่งมอบครั้งนี้ ก่อสร้างแล้วเสร็จเมื่อวันที่</div> <div><input type="checkbox"/> งานแล้วเสร็จภายในกำหนดเวลาตามสัญญา</div> <div><input type="checkbox"/> งานแล้วเสร็จช้ากว่ากำหนดตามสัญญา.....วัน</div> <div>ลงชื่อ ผู้ควบคุมงาน</div> <div>() ตำแหน่ง</div> <div>วันที่</div>			
		จำนวน	หน่วย	ราคาติดตั้ง/ทดสอบต่อหน่วย	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)					
0	PART A งานติดตั้งอุปกรณ์สถานีไฟฟ้า															
0	115 kV Gas Insulated Switchgear															
0	- 123 kV, Gas Insulated Switchgear, 2500 A, 40 kA (Line Bay)	1	Set	114,000.00	114,000.00		-		-		-					
114000	- 123 kV, Gas Insulated Switchgear, 2500 A, 40 kA (TP Bay)	2	Set	114,000.00	228,000.00		-		-		-					
342000	- Local control panel	3	Set	Include	Include		-		-		-					
342000	- steel support structure	1	Lot	Include	Include		-		-		-					
342000	- 115 kV Indoor terminator kit for 115 kV GIS, 800 sq.mm H.V. power cable : 3pcs./set	2	Set	171,000.00	342,000.00		-		-		-					
684000	- SF6 Filling & SF6 Leakage Test	1	Lot	Include	Include		-		-		-					
684000	- Earthing material for connection to the main earthing system (copper rope plus clamps)	1	Lot	Include	Include		-		-		-					
684000	- Supervision for installation , test and commissioning	1	Lot	Include	Include		-		-		-					
684000	- Control cable between 115 kV GIS and local control panel	1	Lot	Include	Include		-		-		-					
684000	- 115 kV GIS individual test	1	Lot	Include	Include		-		-		-					
684000	- Handle for cranking and wall plate or cubicle for tool storage	1	Lot	Include	Include		-		-		-					
684000	115 kV Outdoor Terminator (at 115 kV UG Riser and TR)															
684000	- 115 kV Outdoor terminator for 800 sq.mm H.V. power cable, polymer insulator, creepage distance 31.5 mm/kV : 3pcs./set	2	Set	188,100.00	376,200.00		-		-		-					
1060200																
1060200	- 115 kV Outdoor terminator supporting structure at TR room (3 phases/set)	1	Set	5,700.00	5,700.00		-		-		-					
1065900	96 kV 10 kA Lightning arrester with counter (at 115 kV UG Riser and TR)															
1065900	- 96 kV 10 kA Lightning arrester, Creepage distance 31.5 mm/kV and insulating base and surge counter	6	Set	17,100.00	102,600.00		-		-		-					
1168500	115 kV Control & Protection Board with annunciator															
1168500	- Line control and protection board	1	Set	8,550.00	8,550.00		-		-		-					
1177050	- Transformer control and protection board	2	Set	8,550.00	17,100.00		-		-		-					
1194150	- Outdoor alarm (horn & siren)	1	Set	285.00	285.00		-		-		-					
1194435	- Software to link between relay and computer to download data, setting from relay	1	Lot	Include	Include		-		-		-					
1194435	- Test plug for testing relay 1 set, metering 1 set	1	Lot	Include	Include		-		-		-					
1194435	Computer-Based Substation Control System (CSCS)															

1194435	- CSCS Panel	1	Set	114,000.00	114,000.00		-		-		-		
1308435	- Workstation for CSCS control	1	Set	2,850.00	2,850.00		-		-		-		
1311285	- Hard wiring, fiber optic, UTP Cable and accessories	1	Lot	Include	Include		-		-		-		
1311285	10 kV Indoor Air Insulated Switchgear 3150 A												
1311285	- 10 kV Incoming cubicle with Potential Transformer (3150A)	2	Unit	5,700.00	11,400.00		-		-		-		
	รวม (1)				1,322,685.00		0.00		0.00		0.00		
เจ้าหน้าที่ผู้ได้รับมอบอำนาจจากผู้รับจ้าง				ผู้ควบคุมงาน									
ลงชื่อ..... () ผู้จัดการโครงการ วันที่				ลงชื่อ..... () ตำแหน่ง วันที่									

ทดลองงานที่มีปัญหา													คำติดตั้งและทดสอบ		งวดที่ 1	
สำหรับผู้รับจ้าง								สำหรับการไฟฟ้าส่วนภูมิภาค								
ลำดับ	รายละเอียด	งานตามสัญญา				ส่งมอบงานครั้งนี้		รวมงานที่ส่งแล้ว (รวมครั้งนี้)		สรุปคณะกรรมการตรวจรับ		หมายเหตุ	<div>เรียน คณะกรรมการตรวจรับงานจ้าง</div> <div><input type="checkbox"/> ผลงานที่ส่งมอบครั้งนี้ มีรายละเอียดครบถ้วนถูกต้องตามข้อกำหนดในสัญญาทุกประการ</div> <div><input type="checkbox"/> ผลงานที่ส่งมอบครั้งนี้ ก่อสร้างแล้วเสร็จเมื่อวันที่</div> <div><input type="checkbox"/> งานแล้วเสร็จภายในกำหนดเวลาตามสัญญา</div> <div><input type="checkbox"/> งานแล้วเสร็จช้ากว่ากำหนดตามสัญญา.....วัน</div> <div>ลงชื่อ ผู้ควบคุมงาน</div> <div>() ตำแหน่ง</div> <div>วันที่</div>			
		จำนวน	หน่วย	ราคาติดตั้ง/ทดสอบต่อหน่วย	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)					
0	- 10 kV Outgoing cubicle (1250A)	16	Unit	5,700.00	91,200.00		-		-		-					
91200	- 10 kV Bus tie cubicle with potential transformer (3150A)	1	Unit	5,700.00	5,700.00		-		-		-					
96900	- 10 kV Disconnecting switch cubicle with potential transformer (3150A)	1	Unit	5,700.00	5,700.00		-		-		-					
102600	- 10 kV Load break switch (630A) Cubicle with fuse	1	Unit	5,700.00	5,700.00		-		-		-					
108300	- Arc detection system (fiber optic 3 compartment per 1 cubicle),	1	Lot	Include	Include		-		-		-					
108300	- Heater in 4 compartment per cubicle, Cable gland	1	Lot	Include	Include		-		-		-					
108300	- Supervisor for installation and support site test	1	Lot	Include	Include		-		-		-					
108300	- Wall plate for tool storage	1	Lot	Include	Include		-		-		-					
108300	- C base fame support 10 kV switchgear equipment	1	Lot	Include	Include		-		-		-					
108300	- Handle for cranking, Mobile Truck	1	Lot	Include	Include		-		-		-					
108300	- Software to link between relay and computer to download data, setting from relay	1	Lot	Include	Include		-		-		-					
108300	- Test plug for testing relay 1 set, metering 1 set	1	Lot	Include	Include		-		-		-					
108300	Power Transformer															
108300	- 115/10 kV 3 phase ONAN/ONAF 25/27.5 MVA , Dyn1 with automatic OLTC with oil purifier for OLTC,	1	Unit	285,000.00	285,000.00		-		-		-					
393300	CT core in MV for winding temp and AVR, N bushing for protection															
393300	- Local control cubicle with lamp indicator and annanciator	1	Unit	Include	Include		-		-		-					
393300	10/0.4 kV Station Service Transformer															
393300	- Station service transformer, oil-immersed type,three-phase , 100 kVA, Dyn11, 10,000-400/230 VAC	1	Set	3,990.00	3,990.00		-		-		-					
397290	with cable connection boxes															
397290	AC and DC Distribution Board															
397290	- AC Distribution Board (2 main CB, 30 branch circuits), Floor type	1	Set	2,850.00	2,850.00		-		-		-					
400140	- DC Distribution Board (2 main CB, 30 branch circuits), Floor type	1	Set	2,850.00	2,850.00		-		-		-					
402990	Battery & Battery Charger For 125 VDC															
402990	- Sealed Lead Acid Type Battery > 110 Ah 12V/block 125Vdc	1	Lot	2,850.00	2,850.00		-		-		-					
405840	- Steel Support for battery	1	Lot	Include	Include		-		-		-					
405840	- Battery Charger 30 A with automatic dropper switch	2	Set	2,850.00	5,700.00		-		-		-					

411540	- Safety switch with fuse	1	Set	1,710.00	1,710.00		-		-		-		
413250	Power Cable & Termination kit												
413250	- H.V. power cable, 800 sq.mm., 115 kV, for connecting between 115 kV UG riser and 115 kV indoor GIS	1	Lot	87,210.00	87,210.00		-		-		-		
500460	(3 wires/phase)												
	รวม (2)			500,460.00		0.00		0.00		0.00			
เจ้าหน้าที่ผู้ได้รับมอบอำนาจจากผู้รับจ้าง				ผู้ควบคุมงาน									
ลงชื่อ.....				ลงชื่อ.....									
() ผู้จัดการโครงการ				() ตำแหน่ง									
วันที่				วันที่									

ทดลองงานที่มีปัญหา													คำติดตั้งและทดสอบ		งวดที่ 1	
สำหรับผู้รับจ้าง								สำหรับการไฟฟ้าส่วนภูมิภาค								
ลำดับ	รายละเอียด	งานตามสัญญา				ส่งมอบงานครั้งนี้		รวมงานที่ส่งแล้ว (รวมครั้งนี้)		สรุปคณะกรรมการตรวจรับ		หมายเหตุ	<div>เรียน คณะกรรมการตรวจรับงานจ้าง</div> <div><input type="checkbox"/> ผลงานที่ส่งมอบครั้งนี้ มีรายละเอียดครบถ้วนถูกต้องตามข้อกำหนดในสัญญาทุกประการ</div> <div><input type="checkbox"/> ผลงานที่ส่งมอบครั้งนี้ ก่อสร้างแล้วเสร็จเมื่อวันที่</div> <div><input type="checkbox"/> งานแล้วเสร็จภายในกำหนดเวลาตามสัญญา</div> <div><input type="checkbox"/> งานแล้วเสร็จช้ากว่ากำหนดตามสัญญา.....วัน</div> <div>ลงชื่อ ผู้ควบคุมงาน</div> <div>() ตำแหน่ง</div> <div>วันที่</div>			
		จำนวน	หน่วย	ราคาติดตั้ง/ทดสอบต่อหน่วย	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)					
0	- H.V. power cable, 800 sq.mm., 115 kV, for connecting between 115 kV indoor GIS and power transformers	1	Lot	17,100.00	17,100.00		-		-		-					
17100	(3 wires/phase)															
17100	- H.V. power cable, 500 sq.mm., 10 kV, for connecting between power transformer and 10 kV switchgear	1	Lot	37,962.00	37,962.00		-		-		-					
55062	incoming cubicle (3 wires/phase)															
55062	- H.V. power cable, 500 sq.mm., 10 kV, for connecting between 10 kV switchgear bus tie circuit breaker cubicle	1	Lot	25,650.00	25,650.00		-		-		-					
80712	and 10 kV switchgear disconnecting switch cubicle (3 wires/phase)															
80712	- H.V. power cable, 50 sq.mm., 10 kV, for connecting between 10 kV switchgear load break switch cubicle	1	Lot	3,648.00	3,648.00		-		-		-					
84360	and station service transformer (1 wire/phase)															
84360	- Outdoor cable termination kit, for H.V. power cable, 500 sq.mm., 10 kV, completed with accessories.	9	Set	2,280.00	20,520.00		-		-		-					
104880	- Outdoor cable termination kit, for H.V. power cable, 50 sq.mm., 10 kV, completed with accessories.	3	Set	2,280.00	6,840.00		-		-		-					
111720	- Indoor cable termination kit, for H.V. power cable, 500 sq.mm., 10 kV, completed with accessories.	27	Set	2,280.00	61,560.00		-		-		-					
173280	- Indoor cable termination kit, for H.V. power cable, 50 sq.mm., 10 kV, completed with accessories.	3	Set	2,280.00	6,840.00		-		-		-					
180120	- Steel support for H.V. power cable under 10 kV switchgear (all cubicle) completed with wooden clamp	1	Lot	28,500.00	28,500.00		-		-		-					
208620	Aluminium Conductor & accessories															
208620	- Stranded conductor, aluminium conductor 400 SQ.mm. and accessories,	1	Lot	1,140.00	1,140.00		-		-		-					
209760	for connecting between outdoor cable terminator kit and power transformer, lightning arrester															
209760	- Substation connectors.	1	Lot	4,560.00	4,560.00		-		-		-					
214320	- Stranded conductor accessories.	1	Lot	1,140.00	1,140.00		-		-		-					
215460	Cable Ladder & conduit for substation															
215460	- Rigid steel conduits, fittings and accessories	1	Lot	5,700.00	5,700.00		-		-		-					
221160	- Cable tray and cable ladder & fixing material	1	Lot	91,200.00	91,200.00		-		-		-					
312360	- Identification plates and danger notice	1	Lot	5,700.00	5,700.00		-		-		-					
318060	- Other necessary materials	1	Lot	7,000.00	7,000.00		-		-		-					
325060	Grounding System															
325060	- Lightning protection	1	Lot	57,000.00	57,000.00		-		-		-					
382060	- Ground bar, PVC, RSC and accessories	1	Lot	2,850.00	2,850.00		-		-		-					
384910	- Ground mesh for 115/10 kV substation	1	Lot	9,120.00	9,120.00		-		-		-					

394030	- Ground rod, copper cover steel, dia. 16 mm. 3 m. long	1	Lot	17,100.00	17,100.00		-		-		-		
411130	- Conductor, copper, Bare 120 sq.mm.	1	Lot	228,000.00	228,000.00		-		-		-		
639130	- Earthing test pit.	2	Unit	912.00	1,824.00		-		-		-		
	รวม (3)				640,954.00		0.00		0.00		0.00		
เจ้าหน้าที่ผู้ได้รับมอบอำนาจจากผู้จ้าง				ผู้ควบคุมงาน									
ลงชื่อ.....				ลงชื่อ.....									
() ผู้จัดการโครงการ				() ตำแหน่ง									
วันที่				วันที่									

60												
2461260	Sub-soil test from ground surface to not less than 30.00 m. depth.	2	Bores	3,420.00	6,840.00		-		-		-	
2468100	Control building											
2468100	- Piling work include dynamic test (design by contractor)	1	Lot	235,980.00	235,980.00		-		-		-	
	รวม (4)			2,704,080.00		0.00		0.00		0.00		
เจ้าหน้าที่ผู้ได้รับมอบอำนาจจากผู้รับจ้าง		ผู้ควบคุมงาน										
ลงชื่อ.....		ลงชื่อ.....										
() ผู้จัดการโครงการ		() ตำแหน่ง										
วันที่		วันที่										

ทดลองงานที่มีปัญหา												
สัญญาเลขที่ ทดลอง ลงวันที่ จำนวนเงินตามสัญญา 0 บาท (ไม่รวมภาษีมูลค่าเพิ่ม) ผู้รับจ้าง สีเสภากรโยธา กำหนดแล้วเสร็จตามสัญญา วันที่												
คำติดตั้งและทดสอบ												
งวดที่ 1												
สำหรับผู้รับจ้าง												
สำหรับการไฟฟ้าส่วนภูมิภาค												
ลำดับ	รายละเอียด	งานตามสัญญา				ส่งมอบงานครั้งนี้		รวมงานที่ส่งแล้ว (รวมครั้งนี้)		สรุปคณะกรรมการตรวจรับ		หมายเหตุ
		จำนวน	หน่วย	ราคาติดตั้ง/ทดสอบต่อหน่วย	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)	
0	- Control building (not less than 14 x 18 Sq.mm.)	1	Lot	3,933,000.00	3,933,000.00		-		-		-	
3933000	- Epoxy floor (green/red color), self leveling	1	Lot	18,058.00	18,058.00		-		-		-	
3951058	- Power transformer room (Fire protection)	2	Set	263,819.00	527,638.00		-		-		-	
4478696	- Conduit for lightning protection	1	Lot	2,850.00	2,850.00		-		-		-	
4481546	- Earthing system in control building (steel strip size 25 x 4 mm)	1	Lot	31,361.00	31,361.00		-		-		-	
4512907	- Piping and drainage system	1	Lot	193,800.00	193,800.00		-		-		-	
4706707	- 3-Direction electric overhead crane 5 tons in 115 kV GIS room	1	Set	57,000.00	57,000.00		-		-		-	
4763707	Facility for control building											
4763707	- Load center 18 CKT with main CB 60 AT, 3P	1	Set	1,710.00	1,710.00		-		-		-	
4765417	- 1 x T8 16 watt LED lighting fixture (WP) in 115 kV GIS room	16	Set	570.00	9,120.00		-		-		-	
4774537	- 2 x T8 16 watt LED lighting fixture with Aluminum Louver in control room	12	Set	570.00	6,840.00		-		-		-	
4781377	- 2 x T8 16 watt LED lighting fixture with Acylic ditnser in 10 kV SWG room	18	Set	570.00	10,260.00		-		-		-	
4791637	- 2 x T8 16 watt LED lighting fixture, Explosion proof light in battery room	1	Set	570.00	570.00		-		-		-	
4792207	- 1 x T8 16 watt LED lighting fixture bare type in Cable room	30	Set	570.00	17,100.00		-		-		-	
4809307	- 2 x T8 16 watt LED lighting fixture (WP) in Porch area around building	20	Set	570.00	11,400.00		-		-		-	
4820707	- 100 watt LED floodlight luminaires, in power transformer room	4	Set	1,710.00	6,840.00		-		-		-	
4827547	- Receptacle	20	Set	91.00	1,820.00		-		-		-	
4829367	- Power plug 3P+N+G 20A at 115 kV GIS & 10 kV SWG Room	2	Set	285.00	570.00		-		-		-	
4829937	- Safety switch for CDU (Air condition)	5	Set	1,710.00	8,550.00		-		-		-	
4838487	- Air condition 36,000 Btu (control room 2 set and 10kV SWG room 3 set)	5	Set	9,120.00	45,600.00		-		-		-	
4884087	- Air condition timer control panel	1	Set	2,850.00	2,850.00		-		-		-	
4886937	- Ventilation (Fan) + hood for rain protection in control building	1	Lot	28,500.00	28,500.00		-		-		-	
4915437	- Emergency lighting 2x50 w	10	Set	285.00	2,850.00		-		-		-	
4918287	- Emergency exiting	5	Set	285.00	1,425.00		-		-		-	
4919712	- Switch, wire, conductor, conduits and accessories	1	Lot	45,600.00	45,600.00		-		-		-	
49653	- Steel roller door (Moter driver)	3	Set	13,680.00	41,040.00		-		-		-	

เรียน คณะกรรมการตรวจรับงานจ้าง

☐ ผลงานที่ส่งมอบครั้งนี้ มีรายละเอียดครบถ้วนถูกต้องตามข้อกำหนดในสัญญาทุกประการ

☐ ผลงานที่ส่งมอบครั้งนี้ ก่อสร้างแล้วเสร็จเมื่อวันที่

☐ งานแล้วเสร็จภายในกำหนดเวลาตามสัญญา

☐ งานแล้วเสร็จช้ากว่ากำหนดตามสัญญา.....วัน

ลงชื่อ ผู้ควบคุมงาน

() ตำแหน่ง

วันที่

เรียน คณะกรรมการตรวจรับงานจ้าง
☐ ผลงานที่ส่งมอบครั้งนี้ มีรายละเอียดครบถ้วนถูกต้องตามข้อกำหนดในสัญญาทุกประการ
☐ ผลงานที่ส่งมอบครั้งนี้ ก่อสร้างแล้วเสร็จเมื่อวันที่
☐ งานแล้วเสร็จภายในกำหนดเวลาตามสัญญา
☐ งานแล้วเสร็จช้ากว่ากำหนดตามสัญญา.....วัน
ลงชื่อ ผู้ควบคุมงาน
() ตำแหน่ง
วันที่

12												
50063 52	- Fire extinguisher (CO2)	6	Set	570.00	3,420.00		-		-		-	
50097 72	Fire alarm system & fire protection system											
50097 72	- Hardwire system 5 Zone (Manual ,Detector)	1	Set	1,710.00	1,710.00		-		-		-	
50114 82	- Smoke detector (Control building)	14	Set	285.00	3,990.00		-		-		-	
	รวม (5)			5,015,472.00		0.00		0.00		0.00		
เจ้าหน้าที่ผู้ได้รับมอบอำนาจจากผู้รับจ้าง		ผู้ควบคุมงาน										
ลงชื่อ.....		ลงชื่อ.....										
() ผู้จัดการโครงการ		() ตำแหน่ง										
วันที่		วันที่										

ทดลองงานที่มีปัญหา															
สัญญาเลขที่ ทดลอง ลงวันที่ จำนวนเงินตามสัญญา 0 บาท (ไม่รวมภาษีมูลค่าเพิ่ม) ผู้รับจ้าง สีเสภากรโยธา กำหนดแล้วเสร็จตามสัญญา วันที่										ค่าติดตั้งและทดสอบ		งวดที่ 1			
สำหรับผู้รับจ้าง										สำหรับการไฟฟ้าส่วนภูมิภาค					
ลำดับ	รายละเอียด	งานตามสัญญา				ส่งมอบงานครั้งนี้		รวมงานที่ส่งแล้ว (รวมครั้งนี้)		สรุปคณะกรรมการตรวจรับ		หมายเหตุ	เรียน คณะกรรมการตรวจรับงานจ้าง <input type="checkbox"/> ผลงานที่ส่งมอบครั้งนี้ มีรายละเอียดครบถ้วนถูกต้องตามข้อกำหนดในสัญญาทุกประการ <input type="checkbox"/> ผลงานที่ส่งมอบครั้งนี้ ก่อสร้างแล้วเสร็จเมื่อวันที่ <input type="checkbox"/> งานแล้วเสร็จภายในกำหนดเวลาตามสัญญา <input type="checkbox"/> งานแล้วเสร็จช้ากว่ากำหนดตามสัญญา.....วัน ลงชื่อ ผู้ควบคุมงาน () ตำแหน่ง วันที่		
		จำนวน	หน่วย	ราคาติดตั้ง/ทดสอบ ต่อหน่วย	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)				
0	- Heat detector (Battery room)	1	set	285.00	285.00		-		-		-				
285	- Manual detector	6	set	285.00	1,710.00		-		-		-				
1995	- Bell alarm	3	Set	285.00	855.00		-		-		-				
2850	- Fire resistance wire conductor, wire conductor, conduits and accessories	1	Lot	17,100.00	17,100.00		-		-		-				
19950	115-10 kV Transformer foundation with RC. oil gutter.	2	Set	285,000.00	570,000.00		-		-		-				
589950	Steel cover around of RC. Oil gutter around transformer gutter	2	Set	22,800.00	45,600.00		-		-		-				
635550	Oil collecting pit and oil separator capacity not less than 25 cu.m., on pile	1	Set	171,000.00	171,000.00		-		-		-				
806550	2 set of steel pipes dia 6 inch	10	m	570.00	5,700.00		-		-		-				
812250	Station service transformer foundation	1	Set	13,680.00	13,680.00		-		-		-				
825930	Lamp Post Foundation on pile	6	Set	9,120.00	54,720.00		-		-		-				
880650	Cable trench Type A with steel cover, size 1.20 m	30	m	2,052.00	61,560.00		-		-		-				
942210	HDPE Dia 63 mm. PN8 and accessories (for Lamp circuit)	1	Lot	1,710.00	1,710.00		-		-		-				
943920	Crushed rock no.2 surfacing on area 23x31 Sq.mm., 0.10 m hight with concrete curve	1	Lot	15,504.00	15,504.00		-		-		-				
959424	RC pipe, PVC. pipe and RC manhole (All drainage system from control building, RC trench, oil collecting pit and oil separator etc.)	1	Lot	193,800.00	193,800.00		-		-		-				
115324	Wire mesh fence with door for power transformer	2	Set	45,600.00	91,200.00		-		-		-				
1244424	Concrete with wire mesh fence on pile	100	m	2,950.00	295,000.00		-		-		-				
1539424	Mesh gate (1 set x Rolling door) 6 m width	2	set	57,000.00	114,000.00		-		-		-				
1653424	Civil engineering design and construction permissive fee (architech , civil , electrical)	1	Lot	513,000.00	513,000.00		-		-		-				
2166424	Temporary fence and toilet	1	Lot	45,600.00	45,600.00		-		-		-				
2212024	PART C งานก่อสร้างสายส่งระบบ 115 เควี														
2212024	Pole concrete 22.00 m. long with ground plate	8	each	17,100.00	136,800.00		-		-		-				
2348824	Foundation for pole concrete 22.00 m. long,														
2348824	- F1/1 or F6 with grounding (by contractor design)	8	Set	11,400.00	91,200.00		-		-		-				
2440024	Top pole installation														
2440024	- SS-SW-2 (exclude 115 kV Air break switch)	1	set	84,360.00	84,360.00		-		-		-				
2524384	- SS-TG-5	2	set	30,552.00	61,104.00		-		-		-				
2585488	- SS-TG-2	3	set	30,552.00	91,656.00		-		-		-				

26771 44	- SS-UG-1 (exclude terminator and lightning arrester)	1	set	279,300.00	279,300.00		-		-		-		
29564 44	115 kV Air Break Switch												
29564 44	- 123 kV, 2000 A, 40 kA Air break switch with steel support structure and operating platform	1	Set	70,110.00	70,110.00		-		-		-		
	รวม (6)				3,026,554.00		0.00		0.00		0.00		
เจ้าหน้าที่ผู้ได้รับมอบอำนาจจากผู้รับจ้าง ลงชื่อ..... () ผู้จัดการโครงการ วันที่				ผู้ควบคุมงาน ลงชื่อ..... () ตำแหน่ง วันที่									

[illegible]

เจ้าหน้าที่ผู้ได้รับมอบอำนาจจากผู้รับจ้าง	ผู้ควบคุมงาน	รวมเป็นจำนวนเงินที่เบิก 100%	0.00	อนุมัติ
ลงชื่อ..... () ผู้จัดการโครงการ	ลงชื่อ..... () ตำแหน่ง			ลงชื่อ..... (.....)
วันที่	วันที่			วันที่