

ทดลอง 2 หน้า															
สัญญาเลขที่ ทดสอบ22/2563 ลงวันที่ 3 ก.ย. 2562 จำนวนเงินตามสัญญา 40,000,000 บาท (ไม่รวมภาษีมูลค่าเพิ่ม) ผู้รับจ้าง บริษัท ไทยพัฒนา กำหนดแล้วเสร็จตามสัญญา วันที่ 3 ก.ย. 2562										คำอุปกรณ์ ค่าขนส่ง ค่าติดตั้งและทดสอบ			งวดที่ 1		
งานลดณะ															
สำหรับผู้รับจ้าง										สำหรับการไฟฟ้าส่วนภูมิภาค					
ลำดับ	รายละเอียด	จำนวน	หน่วย	คำอุปกรณ์ ต่อหน่วย	ค่าขนส่ง ต่อหน่วย	ค่าติดตั้ง/ทดสอบ ต่อหน่วย	เป็นเงิน (บาท)	จำนวน	เป็นเงิน (บาท)	รวมงานที่ส่งแล้ว (รวมครั้งนี้)	เป็นเงิน (บาท)	สรุปคณะกรรมการตรวจรับ	เป็นเงิน (บาท)	หมายเหตุ	เรียน คณะกรรมการตรวจรับงานจ้าง <input type="checkbox"/> ผลงานที่ส่งมอบครั้งนี้ มีรายละเอียดครบถ้วนถูกต้องตามข้อกำหนดในสัญญาทุกประการ <input type="checkbox"/> ผลงานที่ส่งมอบครั้งนี้ ก่อสร้างแล้วเสร็จเมื่อวันที่ <input type="checkbox"/> งานแล้วเสร็จภายในกำหนดเวลาตามสัญญา <input type="checkbox"/> งานแล้วเสร็จช้ากว่ากำหนดตามสัญญา.....วัน ลงชื่อ ผู้ควบคุมงาน นายควบคุม ตำแหน่ง วิศวกร วันที่
	PART A อุปกรณ์สถานีไฟฟ้า														
1	115 kV Tower incoming structure (Take off structure)														
	- 115 kV. Take-off structure, beam.	1	Set	1,000.00	500.00	500.00	2,000.00		-		-		-		
	- 115 kV. Take-off structure, column.	2	Set	2,000.00	1,000.00	1,000.00	8,000.00		-		-		-		
	- Insulator, suspension type, class 52-3, for 115 kV string assemblies.	6	Set	3,000.00	2,000.00	1,500.00	39,000.00		-	2	13,000.00		-		
	- 250 watt, area LED floodlight luminaires and accessories	2	Set	1,000.00	500.00	500.00	4,000.00		-		-		-		
2	115 kV Disconnecting with grounding switch and support structure														
	- 123 kV, 1250A 40kA Disconnecting switch, three-pole, double side break with grounding	1	Set	By PEA			By PEA		-		-		-		
	creepage 25 mm/kV., handle for cranking and tools														
	- 115 kV Disconnecting switch supporting structure	1	Set						-		-		-		
	- Operating platform	2	Set						-		-		-		
3	115 kV Current transformer														
	- 115 kV Current transformer, single-phase, 4 cores, 40kA and creepage 25 mm/kV	3	Set	By PEA			By PEA		-		-		-		
	- 115 kV Current transformer supporting structure	3	Set						-		-		-		
	- Junction box for 115 kV current transformer	1	Unit						-		-		-		
	- Junction box supporting structure	1	Set						-		-		-		
4	115 kV Inductive voltage transformer														
	- 115 kV Inductive voltage transformer, single-phase, 3 winding 40kA and creepage 25 mm/kV	3	Set	By PEA			By PEA		-		-		-		
	- 115 kV Inductive voltage transformer supporting structure	3	Set						-		-		-		
	- Junction box for 115 kV inductive voltage transformer	1	Unit						-		-		-		
	- Junction box supporting structure	1	Set						-		-		-		
5	115 kV Gas circuit breaker (SF6)														
	- 115 kV Circuit-breaker, SF6 gas, three-pole, 3150A, 40 kA	1	Set	By PEA			By PEA		-		-		-		
	- 115 kV Circuit-breaker supporting structure	1	Set						-		-		-		
	- Operating platform (2 step stairs)	1	Set						-		-		-		
6	115 kV Control & protection board														
	- Transformer control and protection board	1	Unit	By PEA			By PEA		-		-		-		
	- Outdoor alarm (horn & siren)	1	Set						-		-		-		
7	Power transformer														
	- 115/22 kV, 3 phase, ONAN/ONAF, 50/60 MVA, Dyn1, with automatic OLTC with	1	Unit	By PEA			By PEA		-		-		-		
	oil purifier for OLTC, CT core in MV for winding temp, AVR and N bushing for protection														
	รวม (1)						53,000.00		0.00		13,000.00		0.00		
เจ้าหน้าที่ผู้ได้รับมอบอำนาจจากผู้รับจ้าง		ผู้ควบคุมงาน													
ลงชื่อ.....		ลงชื่อ.....													
นายบริษัท ผู้จัดการโครงการ		นายควบคุม ตำแหน่ง วิศวกร													
วันที่		วันที่													

[illegible]